

CITY COUNCIL OF PORT LOUIS
NOTICE

ONB/CCPL/004/2017-Construction of New Roads

Five (5) Bids were opened on 28th August 2017 as follows:

S. No	Description	Unit	Rate (inclusive of VAT) MUR				
			J. Dookun	Safety Construction Co Ltd	Gamma Civic Ltd	Best care Ltd	Transinvest cons Ltd
	Supply, Lay & Compact Hot Premixed Bituminous Asphalt and Related Works within the City Council Area of Port Louis on an as and when required basis following signature of Contract						
1	(a) Cleaning of road surface, removal of loose materials and cart away	m ²	5	37	24.56	46	42.55
	(b) weeding and cart away (if any)	m ²	5	37	26.53	46	8.05
2	Scarification: Scarifying, loosening and digging of any material from carriageway, shoulder, verge including topsoil, demolition of existing concrete kerbs or wall and any features bordering the carriageway, loading and cart away. Works will also include shaping and compaction of the bottom of excavation to 95% B.S. Heavy compaction or as directed by Engineer and any miscellaneous works arising.	m ³	400	633	869.18	690	369.15

	directed by Engineer and any miscellaneous works arising.						
3	Excavation (in any materials) and cart away	m ³	300	633	522.07	575	369.15
4	Fill with materials from excavation	m ³	75	380	182.01	460	284.05
5	Leveling of depressions with crusher run- 0/20 prior to reshaping and for base course. Works will involve Supply, Lay & compact crusher run- 0/20 as per specifications.	m ³	1560	2429	2095.04	2070	2375.90
6	Supply & Application/Spray Prime Coat 1.2L/m ²	m ²	35	33	72.59	46	51.75
7	Cut Asphalt using asphalt cutter or as approved by the Engineer at straight edge and Patch with Bituminous concrete (0/10), minimum thickness of 50 mm	m ²	680	736	154.37	161	437
8	Milling of Asphalt concrete	m ³	3100	2053	1630.37	6900	2895.70
9	Supply & Application/Spray Tack Coat MC80 cut back bitumen at the rate of 0.6 Kg/m ²	m ²	35	33	33.49	50	36.80
10	Reshaping or Wearing course or Base course as specified - Provide, lay & Roll Hot Premixed Bituminous Concrete Asphalt-0/14.	m ³	8700	14514	10665.74	12075	10676.60
11	Road marking-Hot Melt Thermoplastic type	m ²	600	662	641.52	805	610.65
12	Supply & transport to site & Lay Hot Premixed Bituminous Asphaltic						

	concrete 0/10 according to specifications Application of 40mm thick (minimum thickness after compaction) Hot Premixed Bituminous Asphaltic concrete 0/10 including compacting and leveling for any width & trimming of edges	m ²	630	535	576.90	747.50	368
13	Raising manholes (various dimensions) ≤ 500 x 500 mm	Unit	2000	5750	2592	2070	6831
	> 500 x 500 mm	Unit	2500	5750	4536	1863	6831
14	Raising of Drains/Cross Drains & Reinstatement etc. Works to include Cast in-situ Concrete kerbs (on mass concrete) of dimensions n.e. 200 x 330mm (reinf: 4Y10/ R6-250) with concrete mix class 25, hacking of concrete, dowelling as per site instruction.						
	- Open drain (both borders inclusive)	m	600	2875	1069.20	805	3525.90
	- Covered drain including RC slabs and metal grating (both borders inclusive)	m	1000	2875	1944.96	805	3525.90
15	Felling of Trees Girth- 300-600 mm	unit	1500	8832	7592.40	2875	9108

	Felling of Trees Girth- Above 600 mm	unit	2000	8832	10184.40	2875	14421
16	Associated works						
	(a)Supply and place & compact concrete (m3)						
	- grade 15 concrete(mass)	m ³	3500	5299	4967.37	4500	5879.95
	- grade 25 structural concrete	m ³	4100	5542	5172.66	4500	6145.60
	- grade 30 structural concrete	m ³	4300	5741	5269.67	4600	6297.40
	(b)Formwork: Supply & fixing	m ²	250	662	589.87	60	663.55
	formwork (including striking off)						
	(c)Reinforcement :Supply & fix	kg	46	60	49.14	25	73.60
	(d)Supply, lay & compact crusherun	m ³	1560	2429	2095.04	600	2375.90
	0/31.5	m ³	1500	2134	2016.90	600	1996.40
	(e)Spalls: Supply, lay (size: 100-200) & compact	m ²	75	89	100.12	200	82.80
	(f)Geotextile : Supply & fix as per						

	specifications						
	(g) Precast or cast in situ concrete kerbs as per drawings	m	525	699	740.72	345	1036.15
	Type K1	m	525	1035	943.97	460	914.25
	Type K2	m	525	626	563.60	345	800.40
	Type K3	m	525	506	521.74	460	800.40
	Type K4						

28th August 2017


29/8/18